

BOQ FOR REPAIR, REJUVENITION & RESTORATION OF							
JOB No. 4		Estimated Cost- Rs. 2,40000/ , Earnest Money - Rs. 5000/					
S.No.	Reference	Description of item	Quantity	Unit	Rate	Rate in words	Amount in Rupees
1	Market rate	Repair and rejuvenation of village pond by dewatering standing waste water of 66.8×10^5 Cubic litre (approx.) including cost of all required machinery such as pumps, desiel engine, compressors etc. including their hire and running charges of diesel pumps, generator piping & fittings and cost of fuel and lubricants and wages of pump operator/ helper etc.complete in all respect to carry out the specialized job etc. complete in all respects.	175	Hours			
2		Repair and rejuvenation of village pond by dredging / excavtion /removal of silt, weeds and muck etc. from the village pond having water surface area of 3893.59 sqm. under saturated condntions with in all lead and lifts as given below -					
		a) 1st depth of 1.5m initial rate of excavation same nature of soil under saturated conditions -					
	UP Irrigation/5. b, and 9.a	Earthwork in clearance /cleaning of dys. and minors - Rs. 59.80/ cum Extra for wet earthwork excluding dewatering - Rs. 25.90/ cum	950	cum			
		b) 2nd depth of 1.5m –1½ times initial rate + 1½ times lift under saturated conditions	630	cum			
	c) 3rd depth of 1.5m –2 times initial rate + 2½ times lift under saturated conditions	320	cum				
3	Market rate	Depositing the soil as required in layers not exceeding 20 cm in depth including consolidating each deposited layer by ramming, watering, etc.including dressing of sides to make an embankment/ bund up to 1.5 m height all along the perimeter of the pond	279.25	m			
4		Plantion of local variety of trees/plant's saplings over the bund /embankment along the perimeter of the pond and over the vacant land near the pond for land scaping of the pond and to enhance the village aesthetics.	300	Nos.			
			GRAND TOTAL				

		<p>NOTE : Payment for the work of this contract for which will be made are listed in the BIDDING SCHEDULE and described above. The lump sum price and payment made for each item listed shall constitute full compensation for furnishing all plant, labour, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting safety requirements, tests and reports, and for performing all work required to complete the above mentioned work and no separate payment what so ever shall be made.</p>					
--	--	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--	--	--	--	--